



Phases: to be 2 or to be B?

The question of new timescales

Murrough Landon


3 March 2010

- L1Calo phase 2 → phases B and C?
- Implications for design
- Example timescales
- Organising the work?

Possible Change to Phase 2 Timescale

- In the last two years, phase 2 was delayed by ~4 years
 - Last L1Calo upgrade phone meeting: “it seems so far away”
- Now it may have got earlier again by ~3 years
- Phase B (2017?)
 - Replace Calo electronics, most of ATLAS stays the same
 - Need completely new L1Calo & TP giving L1A in $<3\mu\text{s}$
 - Roughly the “LOCalo” and “LOTopo” in my previous diagrams
 - Need new CTP (talking TTC & GBT, LOA & L1A)
 - Need new ROD \Leftrightarrow DAQ “contract” for Calo/L1Calo RODs
- Phase C (202x?)
 - New ID, FCAL, L1Track/L1MDT triggers, L1A \Rightarrow LOA, new L1A
 - L1Calo \Rightarrow LOCalo, possible refined L1Calo stage
 - L1Topo \Rightarrow LOTopo, new L1Topo including L1Track/L1MDT

Last Months Block Diagram



Design Impact

- Phase B must anticipate Phase C
 - CTP and Calo/L1Calo RODs need to know about LOA and L1A
 - LOA only used in phase C, until then mapped to L1A
 - CTP must provide GBT but continue support for TTC
 - New RODs need new "ROD contract"
 - Calo RODs may need to provide outputs for a future "refined L1Calo" stage years before that is designed
 - Stage B L1Calo/L1Topo must be prepared to provide L0 RoIs to the L1Track trigger years before that is designed
 - L1Calo (and RODs) need to design for new FCAL before that gets finalised and installed
 - etc

Example Timescales (1)

- Suspend disbelief, assume we must install phase B L1Calo during 2017 shutdown
- Consider an imaginary scenario:
 - Assume LHC runs until December 2016
 - Jan 2017: remove existing L1Calo modules and cables
 - Feb 2017: start installing new L1Calo system
 - Must have full system ready on schedule to provide noise/cosmic trigger for testing new Calo FE electronics (unlike last time!)
 - End 2017: new Calo+L1Calo system completely installed, tested and working, ready for beam in Jan 2018 (or earlier?)
- Work backwards...
 - Remember that even our most “realistic” schedules for building the current L1Calo were still hopelessly optimistic

Example Timescales (2)

- 2016

- Full scale test of ROD+LOCalo system outside USA15?
- Spillover of production that should have been finished by now

- 2015

- Final production and testing of new LOCalo/LOTopo system
 - About 100 ATCA modules of about 5 different types
 - Last time production/testing of full system took at least a year
 - Without the need for transatlantic synchronisation and coordination

- 2014

- Final prototypes, full slice test with new Calo RODs
- All those awful but essential reviews (FDRs, PRRs)
- Ready to launch production by the end of the year
 - Preproduction this year?

Example Timescales (3)

- 2013
 - Start full system tests
 - Design and build final prototypes
 - Module specifications and preliminary design reviews
- 2012
 - First real prototypes, final R&D, technology choices?
 - New online software for ATCA based system
 - Write detailed technical design report (TDR)?
 - Need full (preliminary) design details of phase B L1Calo
 - Sufficient detail for phase C to build phase B to be ready for it
- 2010-2011
 - Simulation, design studies, technology R&D
- Provision for unrealistic optimism: start now!

Parallel Working?

- Phase B might still revert to delayed phase 2...
 - So we cannot stop work on current phase 1 ideas
- Or it might not
 - So we need to start taking it more seriously
- However there is much commonality
 - Need experience with ATCA, fast serial links, etc
 - Phase B/C/2 will need topological triggers
 - L0Topo as phase 1 (just calo and muons)
 - Later L1Topo (with calo, muons, tracking)
 - Many topological algorithm ideas will be the same or similar
 - Even though phase B/2 can offer object energies and finer η, ϕ
 - Work on simulation can be widened to cover phase B/C/2